



TREES



Pyrus calleryana 'Capital'



Cupressus sempervirens 'Glausa'



Acmena smithii 'Green Screen'



Lagerstroemia indica x L. fauriei 'Natchez'



Cercis canadensis 'Forest Pansy'

SHRUBS



Acacia cognata 'Mini Cog'



Dieters invidoides



Sedum 'Autumn Joy'



Lomandra confertifolia 'Little Cow'



Buxus sempervirens



Westringea fruticosa Jervis Gem'

PLANT LIST

- Acacia cognata 'Mini Cog'*
- Acmena smithii 'Green Screen'*
- Buxus sempervirens (English Box)*
- Cercis canadensis 'Forest Pansy'*
- Cupressus sempervirens 'Glausa' (Italian Cypress)*
- Dieters invidoides (Wild Iris/Dieters)*
- Lagerstroemia indica x L. fauriei 'Natchez' (Crepe Myrtle)*
- Lomandra confertifolia 'Little Cow' (Lomandra)*
- Sedum 'Autumn Joy' (Stonecrop)*
- Pyrus calleryana 'Capital' (Ornamental Pear)*
- Westringea fruticosa Jervis Gem' (Coastal/Native Rosemary)*

NOTES:

1. Curved slatted iron from removal of back fence to be used for fence to vegetable garden. Curved capping such as split irrigation tubing
2. Timber deck to be constructed at east end of swimming pool for 'dangling'. Outside of deck to be lined in vertical mini-orb (zincalume) to safety standards re climbing/entry
3. Edging to garden beds and between gravel paths and grass to be of cortex steel
4. Horizontal slatted screen to pool equipment (pump)
5. Gravel = Tuscan Toppings - extend to carport area
6. Crazy Paving at pool entrance and sitting/dining area in Wisteria Pergola
7. 1200 x 600 pavers to be layered as stepping stones to house
8. Relocate Clothes Line
9. Add horizontal cladding (spotted Gum) around deck
10. Add handrails to stairs



Crazying Paving/Stepping Stones

Contractors to allow for adequate removal of sub-soil, debris etc. - importation of quality organic planting soils & compost where necessary to allow for adequate root establishment. Allow all plantings to be mulched with added quality organic material.

Contractors to allow for electrical & conduit for power to garden lighting & installation of under mulch drip irrigation system (automated as req'd).

Drainage points to be confirmed on site with contractor and include surface/sub-surface as required.

A full survey has not been undertaken by Karen Harvey Garden Design - Contractor to confirm all dimensions, levels, existing features, etc. during on site visit prior to quoting.

All surface preparations, retaining walls, drainage, storm water discharge, electrical & plumbing works, etc are to meet relevant Australian Standards, Building Regulations, Local Government and statutory body regulations.

Any construction details are given as 'concept details' only and are not intended as or should be substitute for relevant engineering computations. All relevant Planning and Building Permits, Work Cover, Public Liability and other documentation is to be in place prior to commencing any works.

<p>Karen Harvey Garden Design <small>112 Rosewell Road / Warriston ph: 0810112 819 email: karen@karenharvey.com.au</small></p> <p>CONCEPT PLAN - POOL GARDEN</p>			
CLIENT			
PROJECT	Pool Garden/ Rear Garden		
ADDRESS			
SCALE	1:100 @ A2		DATE: 12 February 2019

